

**APPENDIX A
Resurfacing Contract 2026-4
Countywide Major Thoroughfares
B2926
List of Streets**

No.	SCHOOL	ROAD NAME	BEGIN	END	Comm District	LENGTH (LF)	LENGTH (centerline miles)	WIDTH (LF)	TWLT LANE (SY)	TURN LANES (SY)	SIDE STREETS (SY)	PAVEMENT AREA (SY)	TFK CONTROL, COBB CTY CERT PEACE OFFICER CONTROL (LS)	SHOULDER REHAB (SY)	RECYCLED ASPH CONC PATCHING INCL BM & HL (TON)	PERMA PAVE PATCHING (AS-DIRECTED) (TON)	RECYCLED ASPH CONC LEVELING, INCL BM & HL (TON)	RECYC ASP CONC 9.5MM SPRPV TP II, GP2, INCL BM & HL (TON)	RECYC ASP CON 12.5MM SUPERPAVE, GP2 ONLY, IN BM & HL (TON) ** SHUTTLE BUGGY REQUIRED**	
1	Yes	Acworth Due West Rd	North Cobb Pkwy	Stilesboro Rd	1	13,964	2.64	31		8,670	2,375	59,142	414	4,655	See Comments				4,879	
2	Yes	Burnt Hickory Rd	Acworth Due West Rd	Old Mountain Rd	1	7,650	1.45	28		2,040	625	26,466	185	2550	See Comments				2,183	
3		Friendship Church Rd	Villa Rica Rd	Dallas Hwy	1	12,035	2.28	25			1,500	34,929	245	4,012	See Comments				2,882	
4		Atlanta Rd	Ridge Rd	Spring Hill Rd	2	2,456	0.47	60	3,548	3,400	1,500	21,275	149		See Comments				1,755	
5		Cooper Lake Dr	Cooper Lake Rd	Atlanta Rd	2	4,966	0.94	24		2,400	1,500	17,144	120	1,655	See Comments			1,414		
6		Bells Ferry Rd	Shiloh Rd	I-575	3	4,264	0.81	48		8,500	2,000	33,241	233		See Comments				2,742	
7		Providence Rd	Roswell Rd	Roswell Rd	3	6,621	1.25	30		1,360	1,500	24,930	175	2,207	See Comments			2,057		
8		East-West Conn	Powder Springs Rd	Austell Rd	4	10,480	1.98	72		4,986	2,000	90,826	636		See Comments				7,493	
9		Riverside Pkwy	Cityview Dr	Hartman Rd	4	5,930	1.12	65	11,200	2,720	1,250	46,794	328		See Comments				3,861	
		As Directed										253	17	22		1,000	500	500	129	205
						12.94						355,000	2,500	15,100		1,000	500	500	3,600	26,000
Cobb Marietta Water Authority Impacted Roads																				
10	Yes	Mars Hill Church Rd	Mars Hill Rd	Acworth Due West Rd	1	9,326	1.77	29		5,100	2,250	37,401	262	3,109	See Comments				3,086	
11	Yes	Old Stilesboro Rd	Acworth Due West Rd	Old Stilesboro Rd	1	7,905	1.50	29		3,740	1,125	30,337	212	2,635	See Comments				2,503	
		As Directed										13	1	6					12	
						3.27						67,750	475	5,750		0	0	0	0	5,600

APPENDIX A
Resurfacing Contract 2026-4
Countywide Major Thoroughfares
B2926
List of Streets

No.	SCHOOL	ROAD NAME	RECY ASPH CONC 19MM SUPERPAVE, GP1 OR GP2, INCL BM & HL (TON) **SHUTTLE BUGGY REQUIRED**	BITUM TACK COAT (GAL)	MILL ASPHALT CONC PVMT, VARIABLE DEPTH (SY)	6' X 6' QUAD LOOP (EA)	6' X 40' QUAD LOOP (EA)	SOLID TRAFFIC STRIPE 5' WHITE (LM)	SOLID TRAFFIC STRIPE 5' YELLOW (LM)	SKIP TRAFFIC STRIPE 5' WHITE (GLM)	SKIP TRAFFIC STRIPE 5' YELLOW (GLM)	THERMO PVMT MARKING, ARROW TP1 (EA)	THERMO PVMT MARKING, ARROW TP2 (EA)	THERMO PVMT MARKING, ARROW TP3 (EA)	THERMO PVMT MARKING, WORD TP1 ONLY (EA)	THERMO PVMT MARKING, WORD TP3A SCHOOL (EA)	THERMO PVMT MARKING, WORD TP15 YIELD (EA)	THERMO SOLID TRAFFIC STRIPE, 24" WHITE (LF)	THERMO SOLID TRAFFIC STRIPE, 8" WHITE (LF)	THERMO SOLID TRAFFIC STRIPE, 5", WHITE (includes mini-skips at turn lanes) (LM)	THERMO SOLID TRAFFIC STRIPE, 5", YELLOW (includes mini-skips at turn lanes) (LM)	THERMO SKIP TRAFFIC STRIPE, 5", YELLOW (10ft. to 30ft) (GLM)	
1	Yes	Acworth Due West Rd	5,291	5,914	100%	59,142		17	16	0	0			55	3	1	2	24	4,476	5.54	5.39		
2	Yes	Burnt Hickory Rd	2,618	2,647	100%	26,466		9	9	0	0	2	14	2		1		120	1,500	3.15	3.00		
3		Friendship Church Rd	3,677	3,493	100%	34,929		14	14	0	0							225	1,000	4.81	4.66		
4		Atlanta Rd	1,411	2,128	100%	21,275		4	3	4	4		30					300	3,500	1.18	1.03	1.18	
5		Cooper Lake Dr	1,457	1,714	100%	17,144		6	6	0	0		10					255	1,950	2.13	1.98		
6		Bells Ferry Rd	2,501	3,324	100%	33,241		6	5	0	5		45					500	8,280	1.87	1.72		
7		Providence Rd	2,428	2,493	100%	24,930	3	8	8	0	0		10	2				375	3,703	2.76	2.61		
8		East-West Conn	9,222	9,083	100%	90,826	28	47	13	12	0	0	13	127	1			1,410	13,377	4.22	4.07		
9		Riverside Pkwy	3,479	4,679	100%	46,794		8	7	0	0		36	1	5		1	405	6,545	2.50	2.35		
		As Directed	416	25	100%	253		16	20	1	1							11	69	0.34	0.19	0.32	
			32,500	35,500		355,000	28	50	100	100	5	10	15	327	9	6	3	1	3,625	44,400	28.50	27.00	1.50
Cobb Marietta Water Authority Impacted Roads																							
10	Yes	Mars Hill Church Rd	3,306	3,740	100%	37,401		11	11	0	0		25			1		270	2,070	3.79	3.64		
11	Yes	Old Stilesboro Rd	2,802	3,034	100%	30,337		10	9	0	0		16	2		2		195	2,254	3.25	3.10		
		As Directed	93	26		63			1										1	0.46	0.26		
			6,200	6,800		67,800	0	0	21	21	0	0	0	41	2	0	3	0	465	4,325	7.50	7.00	0

APPENDIX A
Resurfacing Contract 2026-4
Countywide Major Thoroughfares
B2926
List of Streets

No.	SCHOOL	ROAD NAME	THERMO SKIP TRAFFIC STRIPE, 5", WHITE (10ft to 30ft) (GLM)	THERMO TRAF STRIPING, WHITE (SY)	THERMO TRAF STRIPING, YELLOW (SY)	RPM TYPE 1 (EA)	RPM TYPE 3 (EA)	PREF PLASTIC SOLID PVMT MKG, 8" SKIP (bridges only) (GLF)	PREF PLASTIC SOLID PVMT MKG, 8" CONTRAST (white - bridges only) (LF)	PREF PLASTIC SOLID PVMT MKG, 8" CONTRAST (yellow - bridges only) (LF)	Comments
1	Yes	Acworth Due West Rd		216	1,495	711	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
2	Yes	Burnt Hickory Rd		134	424	396	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
3		Friendship Church Rd		135		615	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
4		Atlanta Rd	1.18	400	500	136	195				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
5		Cooper Lake Dr				262	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 9.5MM Topping
6		Bells Ferry Rd	1.72	1,300	50	226	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
7		Providence Rd			220	344	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 9.5MM Topping
8		East-West Conn		1,410	450	537	40	480	480	480	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
9		Riverside Pkwy		746		310	40				Mill 3 1/2", and place 2" 19 MM, and 1 1/2" 12.5MM Topping
		As Directed	0.10	19	11	13	10				
			3.00	4,360	3,150	3,550	525	480	480	480	
Cobb Marietta Water Authority Impacted Roads											
10	Yes	Mars Hill Church Rd		40	566	480	40				CCMWA placed 8" 19MM in trenches, in these areas mill 1 1/2" and place 1 1/2" 12.5MM topping. All areas outside of trench caps, mill 3 1/2" and place 2" 19 MM, and 1 1/2" 12.5 MM topping
11	Yes	Old Stilesboro Rd		120	130	410	40				
		As Directed			4	10					
			0	160	700	900	80	0	0	0	