APPENDIX A
2027-4 Resurfacing Contract
Countywide Major Thoroughfares (LMIG)
Project No. B2926
List of Streets

No.	ROAD NAME	BEGIN	END	NIGHT WORK	SCHOOL	9.5 MM	MULTIPLE LANES IN EACH DIRECTION	Comm Distr.	LENGTH (LF)	LENGTH (centerline miles)	WIDTH (LF)	TWLT LANE (SY)	TURN LANES (SY)	SIDE STREETS (SY)	PAVEMENT AREA (SY)
1	Due West Road	Dallas Hwy	Acworth Due West Road		Y			1	6,903	1.31	38	8,963	4,760	1,625	35,531
2	Roberts Boulevard	North Cobb Parkway	Barrett Parkway	Y				1	5,409	1.02	51		5,780	1,625	38,056
3	West Sandtown Road	Macland Road	Villa Rica Road		Y			1	10,660	2.02	24	1,400	6,800	2,000	38,627
4	Barrett Lakes Boulevard	Greers Chapel Road	Barrett Parkway	Y			Y	2	5,251	0.99	64	14,238	5,100	1,125	43,565
5	Cumberland Boulevard	South Cobb Parkway	Interstate North Parkway	Y			Y	2	6,890	1.30	63				48,230
6	Greers Chapel Road	Ridenour Road	North Cobb Parkway	Y				2	1,196	0.23	21		680	125	3,596
7	Parkwood Circle	Windy Ridge Parkway	Powers Ferry Road	Y		Y		2	1,926	0.36	32	1,031	680		8,559
8	Indian Hills Drive	Old Canton Road	Ridgewater Drive			Y		3	6,408	1.21	21				14,952
9	Shallowford Road	Childers Road	Fulton County Line	Y				3	6,038	1.14	30		4,080	750	24,957
10	Wooten Lake Road	Wade Green Road	Shiloh Road					3	6,203	1.17	28		5,234	1,125	25,657
11	East-West Connnector	Cooper Lake Drive	South Cobb Drive	Y			Y	4	10,166	1.93	68		13,500		90,310
12	Hurt Road	Hick Road	Concord Road					4	13,327	2.52	25		9,860	2,250	49,129
	AS DIRECTED														
										15.22					421,169
CITY OF MABLETON															
13	Fontaine Road	Floyd Road	East West Connector	Y				4	14,782	**2.80**	24		3,060	1,250	43,729

APPENDIX A
2027-4 Resurfacing Contract
Countywide Major Thoroughfares (LMIG)
Project No. B2926
List of Streets

No.	ROAD NAME	TFK CONTROL, COBB CTY CERT PEACE OFFICER CONTROL (LUMP)	SHOULDER REHAB (SY)	RECYCLED ASPH CONC PATCHING INCL BM & HL (TON)		PERMA PAVE PATCHING (AS-DIRECTED) (TON)	RECYC ASPH CONC LEVELING, INCL BM & HL (TON)	RECYC ASP CONC 9.5MM SPRPV TP II, GP2, INCL BM & HL (TON)	RECYC ASP CON 12.5MM SUPERPAVE, GP2 ONLY, IN BM & HL (TON) ** SHUTTLE BUGGY REQUIRED**	RECY ASPH CONC 19MM SUPERPAVE, GP1 OR GP2, INCL BM & HL (TON) **SHUTTLE BUGGY REQUIRED**	BITUM TACK COAT (GAL)	HIGH FRICTION SURFACE TREATMENT (SY)	MILL ASPHALT CONC PVMT, VARIABLE DEPTH (SY)	
1	Due West Road	249		**See Comments**					2,931	2,220	3,553		100%	35,531
2	Roberts Boulevard	266		**See Comments**					3,140	3,372	3,806		100%	38,056
3	West Sandtown Road	270	3,553	**See Comments**					3,187	3,127	3,863		100%	38,627
4	Barrett Lakes Boulevard	305		**See Comments**					3,594	2,541	4,357		100%	43,565
5	Cumberland Boulevard	338		**See Comments**					3,979	5,305	4,823		100%	48,230
6	Greers Chapel Road	25	797	**See Comments**					297	307	360		100%	3,596
7	Parkwood Circle	60		**See Comments**				706		753	856		100%	8,559
8	Indian Hills Drive	105		**See Comments**				1,234		1,645	1,495		100%	14,952
9	Shallowford Road	175	1,208	**See Comments**					2,059	2,214	2,496		100%	24,957
10	Wooten Lake Road	180		**See Comments**					2,117	2,123	2,566		100%	25,657
11	East-West Connnector	632	6,100	**See Comments**					7,451	8,449	9,031		100%	90,310
12	Hurt Road	344	100	**See Comments**					4,053	4,072	4,913	1,750	100%	49,129
	AS DIRECTED	52	242		1,000	500	500	60	193	372	383		100%	331
		3,000	**12,000**		**1,000**	**500**	**500**	**2,000**	**33,000**	**36,500**	**42,500**	**1,750**		**421,500**
CITY OF MABLETON														
13	Fontaine Road	**300**	**5,900**	**See Comments**					**3,600**	**4,300**	**4,300**		100%	**43,750**

APPENDIX A
2027-4 Resurfacing Contract
Countywide Major Thoroughfares (LMIG)
Project No. B2926
List of Streets

No.	ROAD NAME	6' X 6' QUAD LOOP (EA)	6' X 40' QUAD LOOP (EA)	SOLID TRAFFIC STRIPE 5" WHITE (LM)	SOLID TRAFFIC STRIPE 5" YELLOW (LM)	SKIP TRAFFIC STRIPE 5" WHITE (GLM)	SKIP TRAFFIC STRIPE 5" YELLOW (GLM)	THERMO PVMT MARKING, ARROW TP1 (EA)	THERMO PVMT MARKING, ARROW TP2 (EA)	THERMO PVMT MARKING, ARROW TP3 (EA)	THERMO PVMT MARKING ARROW TP7 (EA)	THERMO PVMT MARKING, WORD TP1 (ONLY) (EA)	THERMO PVMT MARKING, WORD TP3A (SCHOOL) (EA)	THERMO PVMT MARKING, WORD TP15 (YIELD) (EA)	THERMO SOLID TRAFFIC STRIPE, 24" WHITE (LF)
1	Due West Road	5	1	9.81	8.63		7.86		54	2			1		1,830
2	Roberts Boulevard			7.68	6.76	6.75			43						2,188
3	West Sandtown Road	4		15.14	13.33		1.50		27	3			2		1,403
4	Barrett Lakes Boulevard			7.46	6.56	7.46	7.46		28	8		4		5	1,074
5	Cumberland Boulevard			9.79	8.61	9.79		6	47	5	4	8			2,873
6	Greers Chapel Road			1.70	1.50				4						188
7	Parkwood Circle			2.74	2.41	0.15	2.74		6						473
8	Indian Hills Drive			9.10	8.01				4						105
9	Shallowford Road	2	1	8.58	7.55	0.24			18						448
10	Wooten Lake Road			8.81	7.75	1.11			26	2					1,073
11	East-West Connnector	20	12	14.44	12.71	14.44			58	3	7	2			2,902
12	Hurt Road	3	3	18.93	16.66				24	4					1,306
	AS DIRECTED			0.83	0.53	0.06	0.45								37
		34	**17**	**115.00**	**101.00**	**40.00**	**20.00**	**6**	**339**	**27**	**11**	**14**	**3**	**5**	**15,900**
CITY OF MABLETON															
13	Fontaine Road			**21.00**	**18.00**				**16**	**2**					**640**

APPENDIX A
2027-4 Resurfacing Contract
Countywide Major Thoroughfares (LMIG)
Project No. B2926
List of Streets

No.	ROAD NAME	THERMO SOLID TRAFFIC STRIPE, 8" WHITE (LF)	THERMO SOLID TRAFFIC STRIPE, 6" WHITE (includes mini-skips at turn lanes) (LM)	THERMO SOLID TRAFFIC STRIPE, 6" YELLOW (includes mini-skips at turn lanes) (LM)	THERMO SKIP TRAFFIC STRIPE, 6" WHITE (10ft to 30ft) (GLM)	THERMO SKIP TRAFFIC STRIPE, 6" YELLOW (10ft to 30ft) (GLM)	THERMO TRAF STRIPING, WHITE (SY)	THERMO TRAF STRIPING, YELLOW (SY)	THERMO DASHED TRAFFIC STRIPE, 6" WHITE (2ft to 6ft) (LF)	RPM TYPE 1 (EA)	RPM TYPE 3 (EA)	PREF PLASTIC SOLID PVMT MKG, 8" SKIP (bridges only) (LF)	PREFORM PLASTIC PVT MKG, ARROW TP2 (EA)	PREF PLASTIC SOLID PVMT MKG, 8" CONTRAST (white - bridges only) (LF)	PREF PLASTIC SOLID PVMT MKG, 8" CONTRAST (yellow - bridges only) (LF)
1	Due West Road	3,121	3.27	2.88		2.62	400	100		380	104				
2	Roberts Boulevard	3,358	2.56	2.25	2.25		1,050			297	378				
3	West Sandtown Road	2,297	5.05	4.44		0.50				586	160				
4	Barrett Lakes Boulevard	1,879	2.49	2.19	2.49	2.49	632	115		289	407				
5	Cumberland Boulevard	4,308	3.26	2.87	3.26		534	355		379	534	1,560	6	2,340	1,560
6	Greers Chapel Road	257	0.57	0.50			25	63		66	18				
7	Parkwood Circle	887	0.91	0.80	0.05	0.91		90		106	35				
8	Indian Hills Drive		3.03	2.67						352	96			400	400
9	Shallowford Road	627	2.86	2.52	0.08		150	60		332	101				
10	Wooten Lake Road	1,756	2.94	2.58	0.37		611	607		341	142				
11	East-West Connnector	4,004	4.81	4.24	4.81		400			559	788				
12	Hurt Road	1,772	6.31	5.55			175	100		733	200				
	AS DIRECTED	34	0.94	0.51	0.69	0.48	23	10		229	126	40		60	40
		24,300	**39.00**	**34.00**	**14.00**	**7.00**	**4,000**	**1,500**	**1,000**	**4,650**	**3,089**	**1,600**	**6**	**2,800**	**2,000**

CITY OF MABLETON															
13	Fontaine Road		**7.00**	**6.00**						**792**	**264**				

APPENDIX A
2027-4 Resurfacing Contract
Countywide Major Thoroughfares (LMIG)
Project No. B2926
List of Streets

No.	ROAD NAME	Comments
1	Due West Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
2	Roberts Boulevard	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
3	West Sandtown Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
4	Barrett Lakes Boulevard	To exclude 2" patching 543' West of roundabout & 1500' South of roundabout 14,238 SY
5	Cumberland Boulevard	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
6	Greers Chapel Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
7	Parkwood Circle	No side street crosswalks included, replace crosswalks going across Windy Ridge
8	Indian Hills Drive	Do not pull any side streets
9	Shallowford Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
10	Wooten Lake Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
11	East-West Connnector	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping
12	Hurt Road	Existing High Friction Surface Treatment (HFST) to be replaced (~600 lf)
	AS DIRECTED	

CITY OF MABLETON		
13	Fontaine Road	Mill 3 1/2", and place 2" 19 MM, and 1 1/2" Topping